BENGALURU SOLID WASTE MANAGEMENT LIMITED

TENDER DOCUMENT – KW4

Name of Work - Bio-Enzyme based Odour Suppression and Basic infrastructure development works in and around MSGP processing plants in Doddaballapura Constituency.

BENGALURU SOLID WASTE MANAGEMENT LIMITED

Office of the Deputy General Manager-3, 1st Floor, GBA Building, Thimmaiah Road, Vasanth Nagar, Bengaluru– 560 051.

Phone No: 9886526117

TENDERS FOR THE WORK OF

Sl No	Name of Work	Value of Work (in Lakhs)
1	Bio-Enzyme based Odour Suppression and Basic infrastructure development works in and around MSGP processing plants in Doddaballapura Constituency.	**800.21**

TENDER REFERENCE	No. DGM-3/BSWML/TEND/26/2025-26 Date:12.03.2026.
LAST DATE TO UPLOAD PREBID QUERIES	20.03.2026 on or before 15:00 hrs.
PRE-BID MEETING WILL BE HELD ON	23.03.2026 at 15:00 hrs.
LAST DATE AND TIME FOR RECEIPT OF TENDERS	06.04.2026 on or before 16:00 hrs
TIME AND DATE OF OPENING OF COVER ONE OF TENDERS	07.04.2026 at 16:30 hrs
PLACE OF PRE-BID MEETING WILL BE HELD	Office of the Chief Engineer & Chief General Manager (Tech)-2, BSWML, 1st Floor, GBA Building, Thimmaiah Road, Bengaluru-560051.
TIME AND DATE OF OPENING OF COVER TWO OF TENDERS	Will be intimated to the Qualified Tenderers

Contents

Section	Description	Page No.
1	INVITATION FOR TENDERS (IFT)	3-6
2	INSTRUCTIONS TO TENDERERS (ITT)	7-17
3.	QUALIFICATION INFORMATION	18-21
4.	FORM OF TENDER, LETTER OF ACCEPTANCE, NOTICE TO PROCEED WITH THE WORK AND AGREEMENT FORM	22-25
5.	CONDITIONS OF CONTRACT (CC)	25-33
6.	CONTRACT DATA	38-38
7	SPECIFICATIONS	39-40
8	DRAWINGS	40-40
9.	BILL OF QUANTITIES	41-72
10.	FORMAT OF BANK GUARANTEE FOR SECURITY DEPOSIT	73-73

SECTION 1: INVITATION FOR TENDERS (IFT)

BENGALURU SOLID WASTE MANAGEMENT LIMITED

Office of the Deputy General Manager-2, 1st Floor, GBA Building, Thimmaiah Road, Vasanth Nagar, Bengaluru– 560 051.Email:bswmlee4@gmail.com

****

No.DGM-3/BSWML/TEND/26/2025-26
Date:16.03.2026.

INVITATION FOR SHORT TERM TENDER (IFT)
(Only through GOK KPP Portal Only)

The Deputy General Manager-3, BSWML on behalf of the Managing Director, BSWML, Bengaluru invites the tender from eligible bidders for the works detailed in the table below. The Tender documents can be downloaded from the Karnataka Public Procurement Portal Website (https://kppp.karnataka.gov.in) on payment of prescribed fee noted against each item of work (non-refundable) in the form of e-Payment through Karnataka Public Procurement Portal. The Bidder shall submit the bid through Karnataka Public Procurement Portal. Other details may be seen in the bid document.

Sl. No	Name of the Work	Amount put to tender Rs.in lakhs (Excluding GST)	EMD (in Rupees)	Stipulated Period of Contract
1	Bio-Enzyme based Odour Suppression and Basic infrastructure development works in and around MSGP processing plants in Doddaballapura Constituency.	**800.21**	**8,00,211.00**	**11 Months**

Calendar of Events:

1. Last date to upload pre-bid queries: 20.03.2026 upto 15.00 Hrs. in KPP Portal.
2. Pre bid meeting: 23.03.2026 at 15.00 Hrs at the office of CE & CGM-2 (Tech), BSWML, Thimmaiah Road, Vasanthanagar, Bangalore.
3. Last date for submission of the bids: 06.04.2026 upto 16.00 Hrs.

4. Date of opening of Technical bids on: 07.04.2026 at 16.30 Hrs.
5. Date of opening of Financial bids will be notified to technically qualified bidders.

NOTE:

1. The bidder shall quote rates excluding GST in KPP Portal.
2. No Joint Venture/Consortium is permissible. The validity of tender is 90 days from the date of opening of tender.
3. Aspiring Bidders/Contractors who have not registered in Karnataka Public Procurement Portal should the website (https://kppp.karnataka.gov.in)register before participating through the website (https://kppp.karnataka.gov.in)
4. Before submission of online bids, bidders must ensure that scanned copies of all the necessary documents have been attached with bid.
5. All the required information required for Bids must be filled and submit online.
6. For details, registration and e-payment visit GOK Karnataka Public Procurement Portal website https://kppp.karnataka.gov.in) or contact Karnataka Public Procurement Portal Helpdesk.

Sd/-
Deputy General Manager-3
BSWML, Bengaluru.

Copy Submitted to the:

1. Hon'ble Chairman, BSWML & ACS, UDD for kind information.
2. Hon'ble Managing Director, BSWML/Chief Commissioner, GBA for kind information.
3. Chief Executive Officer, BSWML for kind information.
4. Chief Operational Officer, BSWML, for kind information.
5. Chief Engineer & Chief General Manager-2 (Tech), BSWML, for kind information.
6. Chief Financial officer, BSWML for kind information.
7. Company Secretary, BSWML for kind necessary action.
8. Office Copy.

Deputy General Manager-3
BSWML, Bengaluru.

SECTION 2: INSTRUCTIONS TO TENDERERS (ITT)

Table of Clauses

		Page No.
A.	**General**	
1.	Scope of Tender	8
2.	Eligible Tenderers	8
3.	Qualification of the Tenderer	8
4.	One Tender per Tenderer	10
5.	Cost of Tendering	10
6.	Site Visit	10
B.	**Tender Documents**	
7.	Content of Tender documents	10
8.	Clarification of Tender Document	10
9.	Amendment of Tender documents	10
C.	**Preparation of Tenders**	
10.	Documents comprising the Tender	11
11.	Tender prices	11
12.	Tender validity	11
13.	Earnest money deposit	12
14.	Format and signing of Tender	12
D.	**Submission of Tenders**	
15.	Sealing and marking of Tenders	12
16.	Deadline for submission of Tenders	13
17.	Late Tenders	13
18.	Modification and Withdrawal of Tenders	13
E.	**Tender opening and evaluation**	
19.	Opening of First Cover of all Tenders and evaluation to determine qualified Tenderers	13
20.	Opening of Second Cover Tenders of qualified Tenders and evaluation	14

21. Process to be confidential 14
22. Clarification of Tenders 14
23. Examination of Tenders and determination of responsiveness 14
24. Correction of errors 14
25. Evaluation and comparison of Tenders 15

F. Award of contract

26. Award criteria 15
27. Employer‟s right to accept any Tender and to reject any or all Tenders 15
28. Notification of award and signing of Agreement 15
29. Security deposit 16
30. Advance payment and Security 16
31 Corrupt or Fraudulent Practices 16

A. General

1. Scope of Tender

The Deputy General Manager-3, BSWML, on behalf of the Managing Director, BSWML (Referred to as Employer in these documents) invites ITEM RATE tenders following Two Cover tender procedure, from eligible Tenderers, for the works of "**Bio-Enzyme based Odour Suppression and Basic infrastructure development works in and around MSGP processing plants in Doddaballapura Constituency"** (as defined in these documents and referred to as "the works") detailed in the Table given in the Invitation for Tenders (IFT). The Tenderers may submit tenders for any or all of the works detailed in the table given in IFT.

2. Eligible Tenderers

Tenderers shall not be under a declaration of ineligibility for corrupt and fraudulent practices issued by the Government of Karnataka/GBA. A Bidder shall be any individual, Firm, Agency registered GBA, BDA, NH, PWD, CPWD or other central/state agencies with qualification as set forth in clause 3 below.

Tenders from Joint ventures are not acceptable.

3. Qualification of the Tenderer:

All Tenderers shall provide the requested information accurately and in sufficient detail in

Section 3: Qualification information.

To qualify for award of this contract, each Tenderer in its name should have in the last five financial years (i.e.2020-21 to 2024-25)

(a) Achieved in at least two financial years a minimum financial turnover (in all classes of Civil works and Solid Waste Management works) of **Rs.1647.48 lakhs (**Updated to the FY in which the tenders are invited. Financial turnover of previous years shall be given a weight of 10% per year to bring them to the price level of the FY in which the tenders are invited).

(b) Mandating satisfactorily completion as a prime contractor, at least one similar nature of work in works to as extent of 50% of the cost of the work **(Rs.411.87 lakhs) (**Updated to the FY in which the tenders are invited. The value of the completed works shall be given a weight of 10% per year to bring them to the price level of the FY in which the tenders are invited).

(c) Executed in any one financial year of the last five financial year, the following minimum quantities of work: (usually 80% of the peak annual rate of construction)

SL No	Item	Unit	Qty
1	Earthwork excavation	Cum	7543.73
2	PCC Grade Cement Concrete	Cum	52.30
3	M20 & M30 Grade Cement Concrete	Cum	632.00
4	TMT Steel	Tonnes	60.46
5	GSB	Cum	1142.8
6	WMM	Cum	675.12
7	DBM	Cum	116.4
8	BC	Cum	93.12
9	DLC	Cum	663.00
10	Spraying of Lemon Grass	Ltr	352000.00
11	Total capacity of installed Water Filtration units (not less than 50 LPH each)	LPH	19080

(d) Deleted

(e) Deleted

Each Tenderer should further demonstrate:

(a) Availability by owning at least 50% of the required / specified key and critical equipment for this work and the remaining 50% can be deployed on lease / hire basis for all works provided the relevant documents (commitment agreements etc.) for availability for this work are furnished.

Sl No	Descriptions	Nos	Own/Lease
1	Hot Mix Plant (Minimum capacity of 40/60 TPH)	1	1 Own
2	Mechanical / Sensor paver finisher	1	1 Own
3	Vibratory roller	1	1 Own
4	Static road roller	1	1 Own
5	Tippers	2	2 Own / 1 Own & 1 lease
6	Excavators like JCB/Hitachi	2	2 Own / 1 Own & 1 lease
7	Self-loading Concrete Mixer	1	1 Own
8	Water tanker	2	2 Own / 1 Own & 1 lease

(b) Liquid assets and /or availability of credit facilities of not less than **Rs.224.66 Lakhs** (Credit lines/ letter of credit/ certificates from banks for meeting the fund requirement etc.

To qualify for a package of contracts made up of this and other contracts for which tenders are invited in this IFT, the Tenderer must demonstrate having experience and resources to meet the aggregate of the qualifying

criteria for the individual contracts.
Sub-contractors‟ experience and resources shall not be taken into account in determining the Tenderer's compliance with the qualifying criteria except to the extent stated in 3.2 (d) and (e) above.
Tenderers who meet the above specified minimum qualifying criteria, will only be qualified, if their available tender capacity is more than the total tender value. The available tender capacity will be calculated as under:

Assessed available tender capacity = (A*N*1.5 - B)

Where

A = Maximum Value of Civil Engineering Works executed in any One Year during the last Five years **(updated to 2025-26 Price Level)** taking into account the Completed as well as Works in Progress.

N = Number of years prescribed for Completion of the Works for which Tenders are Invited i.e. 11 Months.

B = Value, at **2025-26 Price Level on 10% Weightage per annum**, of Existing Commitments and on Going Works to be completed during the next 12 months including Monsoon Season.

Note: The statements showing the value of existing commitments and on-going works as well as the stipulated period of completion remaining for each of the works listed should be countersigned by the Employer in charge, not below the rank of an Executive Engineer or equivalent.

Even though the Tenderers meet the above criteria, they are subject to be disqualified if they have:

- made misleading or false representations in the forms, statements and attachments submitted in proof of the qualification requirements; and/or
- record of poor performance such as abandoning the works, not properly completing the contract, inordinate delays in completion, litigation history, or financial failures etc.; and/or
- Participated in the previous Tender for the same work and had quoted unreasonably high tender prices and could not furnish rational justification.

4. One Tender per Tenderer

Each tenderer shall submit only one tender for one package. A tenderer who submits or participates in more than one Tender (other than as a sub-contractor or in cases of alternatives that have been permitted or requested) will cause all the proposals with the Tenderer's participation to be disqualified.

5. Cost of Tendering:

The tenderer shall bear all costs associated with the preparation and submission of his tender, and the Employer will in no case be responsible and liable for those costs.

6. Site visit:

The Tenderer at his own responsibility and risk is encouraged to visit and examine the Site of Works and its surroundings and obtain all information that may be necessary for preparing the Tender and entering into a contract for construction of the Works. The cost of visiting the Site shall be at the Tenderer's own expense.

B. Tender documents

7. Content of Tender documents

The set of tender documents shall have all the Sections given in Page **3**
Both the sets should be completed and returned with the tender.

8. Clarification of Tender Documents

A prospective tenderer requiring any clarification of the tender documents may notify the Employer in writing or by cable (hereinafter "cable" includes telex and facsimile) at the Employer's address indicated in the invitation to tender. The Employer will respond to any request for clarification which he receives earlier than 15 days prior to the deadline for submission of tenders. Copies of the Employer's response will be forwarded to all purchasers of the tender documents, including a description of the enquiry but without identifying its source.

Pre-tender meeting:

The tenderer or his authorized representative is invited to attend a pre-tender meeting which will take place at the Office of the Chief Engineer & Chief General Manager (Tech)-2, BSWML, 1st Floor, GBA Building, Thimmaiah Road, Bengaluru-560051 **on date and time as stipulated in IFT.**

The purpose of the meeting will be to clarify issues and to answer questions on any matter that may be raised at that stage.

The tenderer is requested to submit any questions in writing or by cable to reach the Employer not later than **date and time as stipulated in IFT.**

Minutes of the meeting, including the text of the questions raised (without identifying the source of enquiry) and the responses given will be transmitted without delay to all purchasers of the tender documents. Any modification of the tender documents listed in Sub-Clause 7.1 which may become necessary as a result of the pre-tender meeting shall be made by the Employer exclusively through the issue of an Addendum pursuant to Clause 9 and not through the minutes of the pre-tender meeting.

Non-attendance at the pre-tender meeting will not be a cause for disqualification of a tenderer.

9. Amendment of Tender documents

Before the deadline for submission of tenders, the Employer may modify the tender documents by issuing addenda.
Any addendum thus issued shall be part of the tender documents and shall be communicated in writing or by cable to all the purchasers of the tender documents.
To give prospective Tenderers reasonable time in which to take an addendum into account in preparing their tenders, the Employer shall extend as necessary the deadline for submission of tenders, in accordance with Sub-Clause 16.2 below

C. Preparation of Tenders

10. Documents comprising the Tender

The tender submitted by the Tenderer shall be in two covers and shall contain the documents as follows:

First Cover:

(a) Earnest Money Deposit;
(b) Qualification Information as per formats given in Section 3;

Second Cover:

(a) The Tender (in the format indicated in Section 4)
(b) Priced Bill of Quantities (Section 9);
(c)

and any other materials required to be completed and submitted by Tenderers in accordance with these instructions. The documents listed under Sections 3, 4, 6 and 9 shall be filled in without exception.

Tenderers submitting tenders together with other contracts stated in the IFT to form a package will so indicate in the tender together with any discounts offered for the award of more than one contract.

11. Tender prices

The contract shall be for the whole works as described in Sub-Clause 1.1, based on the priced Bill of Quantities submitted by the Tenderer.
The Tenderer shall fill in rates and prices and line-item total (both in figures and words) for all items of the Works described in the Bill of Quantities along with total tender price (both in figures and words). **Items for which no rate or price is entered by the Tenderer will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of Quantities**. Corrections, if any, shall be made by crossing out, initialing, dating and rewriting.
All duties, taxes, and other levies payable by the contractor under the contract, or for any other cause, shall be included in the rates, prices and total Tender Price submitted by the Tenderer.
The rates and prices quoted by the Tenderer shall be subject to adjustment

during the performance of the Contract in accordance with the provisions of Clause of the Conditions of Contract

12. Tender validity

Tenders shall remain valid for a period not less than **One Hundred Eighty days (180)** after the deadline date for tender submission specified in Clause 16. A tender valid for a shorter period shall be rejected by the Employer as non-responsive.

In exceptional circumstances, prior to expiry of the original time limit, the Employer may request that the Tenderers may extend the period of validity for a specified additional period. The request and the Tenderers' responses shall be made in writing or by cable. A Tenderer may refuse the request without forfeiting his earnest money deposit. A Tenderer agreeing to the request will not be required or permitted to modify his tender, but will be required to extend the validity of his earnest money deposit for a period of the extension, and in compliance with Clause 13 in all respects.

13. Earnest money deposit

The Tenderer shall furnish, as part of his tender, Earnest Money Deposit (EMD) in the amount as mentioned in IFT for this particular Work. Further, out of the total EMD Amount only Rs. 1.00 Lakh (Rupees One Lakh only) shall be paid in the Kpp portal using any of the following modes and the Balance Amount shall be in the form of Bank Guarantee from any nationalized/scheduled Bank.

- Credit Card.
- Direct Debit.
- National Electronic Fund Transfer (NEFT).
- Over the Counter (OTC).

NEFT Payment Procedure:

If a Tenderer chooses to make Payment of EMD / Tender Processing FEE using Reserve Bank of India's (RBI) National Electronic Fund Transfer (NEFT) System, the Tenderer will need to log into kppp, access the Tender for which Bid is being created and then select the NEFT Option under the Payment Section and print the Challan shown in that Section. The Printed Challan will have the Unique Bid Reference Number, Account Details of Government of Karnataka and the Amount to be remitted. The Tenderer shall submit the Printed Challan to its Bank Branch (NEFT enabled) and request for an Account – to – Account Transfer, wherein the money will get transferred from the Tenderer’s Bank Account to GOK‟s Bank Account. The Tenderer shall ensure that NEFT Transfer Instructions are executed and the Funds are wired to the Government of Karnataka's Principal

Account before the Last Date for Bid Submission and preferably 24 hours before the Last Date for Bid Submission. If the Tenderer's Bank transfers / wires the money after the Last Date for Bid Submission, the Tenderer's Bid will be liable for rejection. Upon executing the Transfer, the Tenderer's Bank will provide a Reference Number generated by NEFT Software as Confirmation of Transfer, which has to be input by the Tenderer in the Payment Section of its Bid as Payment Confirmation before the Bid is submitted i.e. as a pre requisite for Bid Submission. The Account Number from which the Funds were transferred shall be input in the KPPP System as part of its Bid also.

OTC Payment Procedure:

If a Tenderer chooses to make Payment of EMD / Tender Processing FEEs Over The Counter (OTC) in any of the designated Axis Bank Branches listed in the KPPP Website (www.kppp.karnataka.gov.in), the Tenderer will need to log into KPPP System, access the Tender for which Bid is being created and then select the OTC Option under the Payment Section and print the Challan shown in that Section. The Printed Challan will have the Unique Bid Reference Number and the Amount to be remitted along with the Challan. The Tenderer can choose to make the Payment either in the form of Cash or in the form of Demand Draft. Cheque Payments will not be accepted. The Tenderer is requested to specifically inform the Bank Officer to input the Unique Bid Reference Number printed in the Challan in the Banking Software. Upon successful Receipt of the Payment, the Bank will provide a 16 Digit Reference Number acknowledging the Receipt of Payment. This 16 Digit Reference Number has to be input by the Tenderer in the Payment Section of its Bid as Payment Confirmation before the Bid is submitted i.e. as a pre requisite for Bid Submission.

The Tenderer shall furnish, as part of his tender, earnest money deposit (EMD) at the following rates

a) upto Rs.20 Lakhs - 2.5%
b) Rs.20 Lakhs and above upto Rs. 1 crore – 2% subject to a minimum of Rs. 50,000/-
c) Rs.1 crore and above upto Rs.10 crores – 1% subject to a minimum of Rs. 2,00,000/-
d) Rs.10 crores and above – 1% subject to a minimum of Rs.15,00,000/-.

e) Fixed Deposit Receipt (FDR) subject to the following condition
   - Maturity date of FDRs issued by the Bank should be beyond the date expected date of finalization of the tender.

Earnest money deposit will have to be in any one of the forms as specified in the Tender document and as per circular PWD:15:ITC:2008/2009 Dated:02-12-2010 (Minimum of Rs.1,00,000/- through e-payment under of the following i.e., online / RTGS / NEFT / OTC and the balance by bank guarantee/FDR issued by Nationalized/ Scheduled Bank and shall have to be valid for 90 days beyond the

validity of the tender.

Instruments having fixed validity issued as earnest money deposit for the tender shall be valid for 90 days **beyond** the validity of the tender.

Any tender not accompanied by an acceptable earnest money deposit and not secured as indicated in Sub-Clauses13.1 and 13.2 above shall be rejected by the Employer as non-responsive.

The earnest money deposit of unsuccessful Tenderers will be returned within 30 days of the end of the tender validity period specified in Sub-Clause 12.1.

The earnest money deposit of the successful Tenderer will be discharged when the Tenderer has signed the Agreement and furnished the required Performance Security.

The earnest money deposit may be forfeited:

(a) if the Tenderer withdraws the Tender after tender opening during the period of tender validity;
(b) if the Tenderer does not accept the correction of the Tender Price, pursuant to Clause 24; or
(c) in the case of a successful Tenderer, if the Tenderer fails within the specified time limit to (i) sign the Agreement; or
(ii) furnish the required Security deposit

14. Format and signing of Tender

Tenderer shall submit the Bid electronically before the submission date and time published in kpp portal.

D. Submission of Tenders

15. Sealing and marking of tenders

Tenderer shall submit the Tender document electronically before the submission date and time published. The document for submission shall be uploaded in PDF format and submitted in the order mentioned below.

1. Content sheet with name of folder / file, No of pages in each folder / file and size of the folder/file.

FIRST COVER /FOLDER (TECHNICAL PART)

2. As per Section 3 - Qualification information
   - **a.** Qualification information summary sheets
   - **b.** Affidavit as per the format attached in qualification information.
   - **c.** Brief description of tenderer with the details of contact person for communication with BSWML
   - **d.** Attested copy of Registration certificate of the contractor
   - **e.** EMD as specified in the Table of I TT in the document.
   - **f.** Power of attorney for signing the tender as per the format attached in

qualification information.

g. Work performed & quantity executed as per Table with supporting certificates from client for the claims mentioned in tables of qualification information.

h. Tables Qualification information with supporting certificate from client &calculation sheet for available tender capacity.

i. Availability of machinery as per Table of qualification information.

j. Experience & qualification of key persons as per Table of qualification information.

k. Financial statement for past five F.Y, contains balance sheet, profit& loss, statement on cash on hand, liquid assets etc from Charted Accountant.

l. Line of credit and details of tenderers bank with reference as per format attached in qualification information.

m. Litigation history as per Table. Of qualification information.

n. Method adopted for construction program, bar chart, quality assurance program as per clause 1.13 of qualification information

o. Undertaking for the tender is valid for 180 days as per clause 1.14 of qualification information.

SECOND COVER/FOLDER (FINANCIAL PART)

a. Form of tender as per section 4 (I) of tender document.

b. Priced Bill of Quantity.

c. Any other materials required to be completed and submitted by Tenderers in accordance with ITT.

Deleted
Deleted

16. Deadline for submission of the Tenders

Tenders must be received by the Employer at the address specified above no later than **4.00PM hours on 06.04.2026** In the event of the specified date for the submission of tenders being declared a holiday for the Employer, the tenders will be received up to the appointed time on the next working day.

The Employer may extend the deadline for submission of tenders by issuing an amendment in accordance with Clause 9, in which case all rights and obligations of the Employer and the Tenderers previously subject to the original deadline will then be subject to the new deadline.

17. Late Tenders

Any Tender received by the Employer after the deadline prescribed in Clause 16 will be returned unopened to the Tenderer.

18. Modification and Withdrawal of Tenders

Tenderers may modify contents of First or Second Covers separately for

each Cover or withdraw their Tenders by giving notice in writing before the deadline prescribed in Clause 16.

Each Tenderer's modification separately for each Cover or withdrawal notice shall be prepared, sealed, marked, and delivered in accordance with Clause 14 & 15, with the outer and inner envelopes additionally marked "**MODIFICATION FOR FIRST/SECOND COVER**" or "**WITHDRAWAL**", as appropriate.

No Tender may be modified after the deadline for submission of Tenders.

Withdrawal or modification of a Tender between the deadline for submission of Tenders and the expiration of the original period of Tender validity specified in Clause 12.1 above or as extended pursuant to Clause 12.2 may result in the forfeiture of the earnest money deposit pursuant to Clause 13.

1 8.5 Tenderers may only offer discounts to, or otherwise modify the prices of their Tenders by submitting Tender modifications in accordance with this clause, or included in the original Tender submission.

E. Tender opening and evaluation

19. Opening of First Cover of all Tenders and evaluation to determine qualified Tenderers:

The Employer will open the First Covers of all the Tenders received (except those received late or withdrawn), including modifications for First Cover made pursuant to Clause 18, in the presence of the Tenderers or their representatives who choose to attend at 07.04.2026 at 4.30 PM on the date and the place specified in Clause 16. In the event of the specified date of Tender opening being declared a holiday for the Employer, the Tenders will be opened at the appointed time and location on the next working day.

Deleted

The Tenderers names, the presence or absence of earnest money deposit (amount, format and validity), the submission of qualification information and such other information as the Employer may consider appropriate will be announced by the Employer at the opening.

The Employer shall prepare minutes of the Tender opening, including the information disclosed to those present in accordance with Sub-Clause 19.3.

Deleted

The Employer will evaluate and determine whether each tender

(a) meets the eligibility criteria defined in ITT Clause 2;

(b) is accompanied by the required earnest money deposit as per stipulations in ITT Clause and

(c) Meets the minimum qualification criteria stipulated in ITT Clause 3.

The Employer will draw out a list of qualified Tenderers.[2]

20. Opening of Second Cover of qualified Tenderers and evaluation:

The Employer will inform all the Qualified Tenderers the time, date and

venue fixed for the opening of the Second Cover containing the priced Tenders. The Employer will open the Second Covers of Qualified Tenderers at the

appointed time and date(as indicated in the Kpp portal) in the presence of the Tenders or their representatives who choose to attend. In the event of the specified date of Second Cover opening being declared a holiday for the Employer, the Second Covers will be opened at the appointed time and location on the next working day.

Deleted

Deleted

The Employer shall prepare minutes of the Second Cover Tender opening.

21. Process to be confidential

Information relating to the examination, clarification, evaluation, and comparison of Tenders and recommendations for the award of a contract shall not be disclosed to Tenderers or any other persons not officially concerned with such process until the award to the successful Tenderer has been announced. Any effort by a Tenderer to influence the Employer's processing of Tenders or award decisions may result in the rejection of his Tender.

22 Clarification of Tenders

To assist in the examination, evaluation, and comparison of Tenders, the Employer may, at his discretion, ask any Tenderer for clarification of his Tender, including breakdowns of unit rates. The request for clarification and the response shall be in writing or by cable, but no change in the price or substance of the Tender shall be sought, offered, or permitted except as required to confirm the correction of arithmetic errors discovered by the Employer in the evaluation of the Tenders in accordance with Clause 24.

Subject to sub-clause 22.1, no Tenderer shall contact the Employer on any matter relating to its Tender from the time of the Tender opening to the time the contract is awarded. If the Tenderer wishes to bring additional information to the notice of the Employer, it should do so in writing.

Any effort by the Tenderer to influence the Employer in the Employer’s Tender evaluation, Tender comparison or contract award decisions may result in the rejection of the Tenderers‟ Tender.

23. Examination of Tenders and determination of responsiveness

Prior to the detailed evaluation of Tenders, the Employer will determine whether each Tender;

(a) has been properly signed; and;

(b) is substantially responsive to the requirements of the Tender documents.

A substantially responsive Tender is one which conforms to all the terms, conditions, and specifications of the Tender documents, without material deviation or reservation. A material deviation or reservation is one

(a) which affects in any substantial way the scope, quality, or performance of the Works;
(b) which limits in any substantial way, inconsistent with the Tender documents, the Employer's rights or the Tenderer's obligations under the Contract; or
(c) whose rectification would affect unfairly the competitive position of other Tenderers presenting substantially responsive Tenders.

If a Tender is not substantially responsive, it will be rejected by the Employer, and may not subsequently be made responsive by correction or withdrawal of the nonconforming deviation or reservation.

24. Correction of errors

The Tenderer may modify the tender only before the last date for submission of the tender, as indicated on the Kpp portal.

25. Evaluation and comparison of Tenders

The Employer will evaluate and compare only the Tenders determined to be substantially responsive in accordance with Clause 23.

Deleted (Since Bids submitted online only)

The Employer reserves the right to accept or reject any variation, deviation, or alternative offer. Variations, deviations, and alternative offers and other factors which are in excess of the requirements of the Tender documents or otherwise result in unsolicited benefits for the Employer shall not be taken into account in Tender evaluation.

The estimated effect of the price adjustment conditions under Clause 41 of the Conditions of Contract, during the implementation of the Contract, will not be taken into account in tender Evaluation

If the tender of the successful tenderer is seriously unbalanced in relation to the Employer’s estimate of the cost of the work to be performed under the contract, the Employer may require the Tenderer to produce detailed price analyses for any or all items of the Bill of Quantities, to demonstrate the internal consistency of those prices with the construction methods and schedule proposed. After evaluation of the price analyses, the Employer may require that the amount of the performance security set forth in Clause 29 be increased at the expense of the successful Tenderer to a level sufficient to protect the Employer against financial loss in the event of default of the successful under the contract.

F. Award of Contract

26. Award criteria

Subject to Clause 27, the Employer will award the Contract to the Tenderer whose Tender has been determined to be substantially responsive to the Tender documents and who has offered the lowest evaluated Tender Price, provided that such Tenderer has been determined to be

(a) eligible in accordance with the provisions of Clause 2, and
(b) qualified in accordance with the provisions of Clause 3.

27. Employer's right to accept any Tender and to reject any or all Tenders

Not with standing Clause 26, the Employer reserves the right to accept or reject any Tender, and to cancel the Tender process and reject all Tenders, at any time prior to the award of Contract, without thereby incurring any liability to the affected Tenderer or Tenderers or any obligation to inform the affected Tenderer or Tenderers of the grounds for the Employer's action.

28. Notification of award and signing of Agreement

The Tenderer whose Tender has been accepted will be notified of the award by the Employer prior to expiration of the Tender validity period by cable, telex, e-mail or facsimile confirmed by registered letter. This letter (hereinafter and in the *Conditions of Contract* called the "Letter of Acceptance") will state the sum that the Employer will pay the Contractor in consideration of the execution, completion, and maintenance of the Works by the Contractor as prescribed by the Contract (hereinafter and in the Contract called the "Contract Price").

The notification of award will constitute the formation of the Contract, subject only to the furnishing of Security deposit in accordance with the provisions of Clause 29.

The Agreement will incorporate all agreements between the Employer and the successful Tenderer. It will be kept ready for signature of the successful Tenderer in the office of Employer within 30 days following the notification of award along with the Letter of Acceptance. Within 20 days of receipt, the successful Tenderer will sign the Agreement and deliver it to the Employer.

Upon the furnishing by the successful Tenderer of the Performance Security, the Employer will promptly notify the other Tenderers that their Tenders have been unsuccessful.

29. Security deposit

Within 20 days of receipt of the Letter of Acceptance, the successful Tenderer shall deliver to the Employer a Security deposit in any of the forms given below for an amount **equivalent to 5% of the Contract price**

plus additional security for unbalanced tenders in accordance with Clause 25.5 of ITT and Clause 44 of the Conditions of Contract for all works.*:*

- Cash or
- Banker's cheque/Demand draft/Pay Order in favor of Managing Director, BSWML payable at Bangalore or
- A bank guarantee in the form given in Section 10; or
- Specified Small Savings Instruments pledged to Managing Director, BSWML payable at Bangalore

If the security deposit is provided by the successful Tenderer in the form of a Bank Guarantee, it shall be issued either by a Nationalized/Scheduled bank.

The security deposit if furnished in cash or demand draft can, if requested, be converted to interest bearing securities at the cost of the successful Tenderer/ contractor.

Failure of the successful Tenderer to comply with the requirements of Sub-Clause 29.1 shall constitute sufficient grounds for cancellation of the award and forfeiture of the Earnest money deposit.

30 Advance Payment and Security:

The Employer will provide an advance payment on the contract price as stipulated in the Conditions of Contract, subject to the maximum amount as stated in the Contract Data.

31 Corrupt or Fraudulent practices

The BSWML requires that the Tenderers/Suppliers/Contractors, observe the highest standard of ethics during the procurement and execution of such contracts. In pursuance of this policy, BSWML :

(a) will reject a proposal for award if it determines that the Tenderer recommended for award has engaged in corrupt or fraudulent practices in competing for the contract in question;

(b) will declare a firm ineligible, either indefinitely or for a stated period of time, to be awarded a BSWML contract if it at any time determines that the firm has engaged in corrupt or fraudulent practices in competing for, or in executing, a BSWML contract.

Furthermore, Tenderers shall be aware of the provision stated in sub-clause 50.2 of the Conditions of Contract.

SECTION 3: QUALIFICATION INFORMATION

The information to be filled in by the Tenderer hereunder will be used for purposes of computing Tender capacity as provided for in Clause 3 of the Instructions to Tenderers. This information will not be incorporated in the Contract.

1.1 Constitution or legal status of Tenderer [Attach copy]

Place of _____
(Attach Copy)

Registration _____

Principal place of

business:

1.2 Total value of civil engineering construction works executed and payments received in the last five years 2020 - 21 .....
2021 - 22 .....
2022 - 23.....
2023 - 24.....
2024 - 25.....

(in Rs. Lakhs) Attach Certificate from Chartered Accountant

1.3 Work performed as Prime Contractor (in the same name) on works of similar nature over during the five years specified in 1.2 above.

Project Name	Name of Employer	Descrip-tion of Work	Contract Number	Value of Contract Rs. Lakhs	Date of issue of work order	Specified period of completion	Actual date of commencement	Remarks explaining reasons for delay in completion of work
1	2	3	4	5	6	7	8	9

1.4 Quantities of work executed as prime contractor (in the same name) during the last five years specified in 1.2 above:

Year	Name of Contractor	Name of	Quantity of work performed (cum)[1]	Remarks

	Work	Employer				(Indicate contract reference)
			Cement Concrete	Masonry	Earthworks	
2020-21						
2021-22						
2022-23						
2023-24						
2024-25						

1.5 Information on works for which Tenders have been submitted and works which are yet to be completed as on the date of this Tender.

(A) Existing commitments and on-going works:

Description of Work	Place & State	Contract No. & Date	Name And Address of Employer	Value of Contract (Rs. lakhs)	Stipulated period of completion	Value of works remaining to be completed (Rs. lakhs) Attach Certificates from Engineers –in-Charge	Anticipated date of completion
1	2	3	4	5	6	7	8

(B) Works for which Tenders already submitted:

Description of Work	Place & State	Name and Address of Employer	Estimated value of works (Rs. lakhs)	Stipulated period of completion	Date when decision is expected	Remarks if any
1	2	3	4	5	6	7

[1] Items of work for which data is requested should tally with that specified in ITT Clause 3

1.6. The following items of equipment are considered essential for successfully carrying out the works. The Tenderer should furnish all the information listed below.

Item of Equipment	**Requirement**		
As mentioned above			

1.7 Reports on the financial standing of the tenderer, such as profit and loss statements and auditor's reports for the last five years;

1.8 Qualification and experience of the key technical and management personnel in permanent employment with the tenderer and those that are proposed to be deployed on this contract, if awarded.

Position	**Names**	**Qualification**	**Year of Experience (General)**	**No's required**
Project Manager		BE in Civil/Environmental Engg.	3-5 Yrs – in Civil Engineering - Construction projects	1
Site Engineer		BE in Civil Engg	5 Yrs – in BE Civil Engineering - Construction projects	3

1.9. Name, address, and telephone, telex, and fax numbers of the Tenderers' bankers who may provide references if contacted by the Employer. Evidence of access to financial resources to meet the qualification requirement specified in ITT Clause3.3 (b): Cash in hand, Letter of Credit etc. List them below and attach certificate from the Banker in the suggested format as under:

1.10 Evidence of access to financial resources to meet the qualification requirement specified in ITT Clause3.3 (b): Cash in hand, Letter of Credit etc. List them below and attach certificate from the Banker in the suggested format as under:

ON BANKS LETTER HEAD

.....

FORMAT OF BANKER'S CERTIFICATE/ LINE OF CREDIT LETTER (TO BE ISSUED IN THE LETTER HEAD OF THE BANK BRANCH)

Reference Number (Sl. No.)

Place:

Date :

To:

(Name of Address of the Beneficiary)

This is to certified that, Mr./ Mrs. ..... (Name of the Customer) having his/ their registered/ Administrative office at ..... Is a customer of our bank and is/ are engaged in ..... (Name of activity). If the said customer is allotted/ awarded with ..... (Brief details of works), we may extend the credit facilities up to Rs. ..... Lakhs to meet his/ their working capital requirement towards the execution of the said work order as per the loan policy of the Bank.

This certificate is valid up to ..... months from the date of issue, i.e. up to dd/mm/yyyy.

Yours faithfully,

Branch Manager.

1.11 Proposals for subcontracting components of works amounting to more than 20% of the contract price.

Item of Work	Value of Sub-Contract	Identified Sub-Contractor (Name and address)	Experience of similar work (Attach certificates from the respective Employers.)
1	2	3	4

1.12 Information on litigations in which the Tenderer is involved:

Other Party (ies)	Employer	Details of dispute	Amount involved	Remarks showing present status

1.13 The proposed methodology and program of construction, backed with equipment planning and deployment, duly supported with broad calculations and quality control procedures proposed to be adopted, justifying their capability of execution and completion of the work as per technical specifications within the stipulated period of completion as per milestones.

SECTION 4: FORMS OF TENDER, LETTER OF ACEPTANCE, NOTICE TO PROCEED WITH THE WORK AND AGREEMENT FORM

Form of Tender

Description of the Works: Bio-Enzyme based Odour Suppression and Basic infrastructure development works in and around MSGP processing plants in Doddaballapura Constituency.

To,

Deputy General Manager-3,
BSWML, 1st Floor, GBA Building, Thimmaiah Road, Vasanth Nagar,
Bangalore-51.

GENTLEMEN,

We offer to execute the Works described above in accordance with the Conditions of Contract accompanying this Tender for the Contract Price of .....*[in figures] ( ) [in letters]*.[4]

This Tender and your written acceptance of it shall constitute a binding contract between us. We understand that you are not bound to accept the lowest or any Tender you receive.

The advance payment required is Rs.....

We undertake that, in competing for (and, if the award is made to us, in executing) the above contract, we will strictly observe the laws against fraud and corruption in force in India namely "Prevention of Corruption Act 1988" hereby confirm that this Tender complies with the Tender validity and Earnest money deposit required by the Tender documents.

We attach herewith our current income-

tax clearance certificate. Yours faithfully,

Authorized Signature:
Name & Title of Signatory: _____

Name of Tenderer _____

Address: .....

[4] To be filled in by the Tenderer, together with his particulars and date of submission at the bottom of the Form of Tender

Letter of Acceptance

(letterhead paper of the Employer)

..... [date]

To:

.....

.....[name and address of the Contractor]

Dear Sir,

This is to notify you that your Tender dated.....for execution of the "Bio-Enzyme based Odour Suppression and Basic infrastructure development works in and around MSGP processing plants in Doddaballapura Constituency" for the .....Contract Price of Rupees..... ..... (.....) [amount in words and figures], as corrected and modified in accordance with the Instructions to Tenderers is hereby accepted by our Agency.

You are hereby requested to furnish Security deposit plus additional security for unbalanced tenders in terms of Clause 25.5 of ITT, in the form detailed in Clause 29.1 of ITT for an amount of Rs.....within 20 days of the receipt of this letter of
Acceptance valid up to 30 days from the date of expiry of Defects Liability Period i.e. up to.....and sign the contract,
Failing which action as stated in Para 29.4 of ITT will be taken.

Yours faithfully,

Authorized Signature Name and Title of Signatory
Name of Agency

Issue of Notice to proceed

with the work

(Letterhead of the Employer) .....(date)

To

.....
.....

..... (name and address of the Contractor)

Dear Sir:

Pursuant to your furnishing the requisite security deposit as stipulated in ITT Clause 29.1 and signing of the contract agreement for the work of **Bio-Enzyme based Odour Suppression and Basic infrastructure development works in and around MSGP processing plants in Doddaballapura Constituency**. A Tender Price of Rs.....you are hereby instructed to proceed with the execution of the said works in accordance with the contract documents.

Yours faithfully,

(Signature, name and title of signatory
Authorized to sign on behalf of Employer)

Agreement Form

Agreement

This agreement, made the .....day of .....20 , between.....
.....[name and address of Employer] (hereinafter called "the Employer") of the one part and .....
.....
.....[name and address of contractor] (hereinafter called "the Contractor") of the other part.

Whereas the Employer is desirous that the Contractor execute .....
.....
..... [name and identification number of Contract] (hereinafter called "the Works") the Employer has accepted the Tender by the Contractor for the execution and completion of such Works and the remedying of any defects therein at a contract price of Rupees'.....

NOW THIS AGREEMENT WITNESSETH as follows:

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to, and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Employer to execute and complete the Works and remedy any defects therein in conformity in all aspects with the provisions of the Contract.
3. The Employer hereby covenants to pay the Contractor in consideration of the execution and completion of the Works and the remedying the defects wherein the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.
4. The following documents shall be deemed to form and be read and construed as part of this Agreement, viz:
   - i) Letter of Acceptance;
   - ii) Notice to proceed with the works;
   - iii) Contractor's Tender;
   - iv) Contract Data;
   - v) Conditions of contract (including Special Conditions of Contract);
   - vi) Specifications;
   - vii) Drawings;
   - viii) Bill of Quantities; and
   - ix) Any other document listed in the Contract Data as forming part of the contract.

In witness whereof the parties thereto have caused this Agreement to be executed the day and year first before written. The Common Seal of

.....
.....
was hereunto affixed in the presence of:
Signed, Sealed and Delivered by the said
.....
.....
in the presence of:
Binding Signature of Employer
Binding Signature of Contractor

SECTION 5: CONDITIONS OF CONTRACT

Table of Contents

A. General **Page No.**

1. Definitions 20
2. Interpretation 20
3. Law governing contract 21
4. Employers decisions 21
5. Delegation 21
6. Communications 21
7. Subcontracting 21
8. Other Contractors 21
9. Personnel 21
10. Employer's and Contractor's risks 21
11. Employer's risks 21
12 Contractor's risks 22
13. Insurance 22
14. Site Investigation Report 22
15 Query about Contract Data 22
16 Contractor to construct the Works 22
17. The Works to be completed by Intended Completion Date 22
18 Approvals by the Employer 22
19. Safety 23
20. Discoveries 23
21. Possession of the Site 23
22. Access to the Site 23
23. Instructions 23
24. Procedure for resolution of disputes 23

B. Time Control

25. Program 23
26. Extension of the Intended Completion Date 24
27. Delays ordered by the Employer 24
28. Management meetings 24

C. Quality Control

29. Identifying defects 24
30. Tests 24
31. Correction of defects 24
32. Uncorrected defects 24

D. Cost Control

33 Bill of Quantities (BOQ) 24
34 Variations 25
35. Payment for Variations 25
36. Submission of bills for payment 25
37 Payments 26
38. Compensation events 26
39. Tax 26
40 Price Adjustment 26
41. Liquidated damages 26
42. Advance Payments 27
43. Securities 27
44. Cost of repairs 27

E Finishing of Contract

45. Completion 27
46. Taking Over 27
47. Final account 27
48. As built drawings and/or Operating and Maintenance Manuals 28
49. Termination 28
50. Payment upon termination 29
51. Property 29
52. Release from performance 29

Conditions of Contract

A. General

1. Definitions

Terms which are defined in the Contract Data are not also defined in the Conditions of Contract but keep their defined meanings. Bold letters are used to identify defined terms.

Bill of Quantities means the priced and completed Bill of Quantities forming part of the Tender.

Compensation events are those defined in Clause 38 hereunder.

The **Completion Date** is the date of completion of the Works as certified by the Employer in accordance with Sub Clause 46.1.

The **Contract** is the contract between the Employer and the Contractor to execute, complete and maintain the Works. It consists of the documents listed in Clause 2.2 below.

The **Contract Data** defines the documents and other information which comprise the Contract.

The **Contractor** is a person or corporate body whose Tender to carry out the Works has been accepted by the Employer.

The **Contractor's Tender** is the completed Tender document submitted by the Contractor to the Employer.

The **Contract price** is the price stated in the Letter of Acceptance and thereafter as adjusted in accordance with the provisions of the Contract.

Days are calendar days; **months** are calendar months.

A **Defect** is any part of the Works not completed in accordance with the Contract.

The **Defects liability period** is the period named in the Contract Data and calculated from the Completion Date which is 12 months for this project.

The **Employer** is the party who will employ the Contractor to carry out the Works.

Equipment is the Contractor's machinery and vehicles brought temporarily to the Site to construct the Works. The **Initial Contract price** is the Contract Price listed in the Employer's Letter of Acceptance.

The **Intended Completion Date** is the date on which it is intended that the Contractor shall complete the Works. The Intended Completion Date is specified in the Contract Data. The Intended Completion Date may be revised only by the Employer by issuing an extension of time.

Maintenance Period is the period named in the Contract Data, during which Contractor shall maintain the works completed by him for a period of 12 months effective from last day of Defect Liability Period

Materials are all supplies, including consumables, used by the contractor for incorporation in the Works.

Plant is any integral part of the Works which is to have a mechanical, electrical, electronic or chemical or biological function.

The **Site** is the area defined as such in the Contract Data.

Specification means the Specification of the Works included in the

Contract and any modification or addition made or approved by the Employer.
The **Start Date** is given in the Contract Data. It is the date when the Contractor shall commence execution of the works. It does not necessarily coincide with any of the Site Possession Dates.
A **Subcontractor** is a person or corporate body who has a Contract with the Contractor to carry out a part of the work in the Contract which includes work on the Site.
A **Variation** is an instruction given by the Employer which varies the Works.
The **Works** are what the Contract requires the Contractor to construct, install, and turn over to the Employer, as defined in the Contract Data.

2. Interpretation

In interpreting these Conditions of Contract, singular also means plural, male also means female or neuter, and the other way around. Headings have no significance. Words have their normal meaning under the language of the Contract unless specifically defined. The Employer will provide instructions clarifying queries about the Conditions of Contract.

The documents forming the Contract shall be interpreted in the following order of priority:

(1) Agreement
(2) Letter of Acceptance, notice to proceed with the works
(3) Contractor's Tender
(4) Contract Data
(5) Conditions of Contract
(6) Specifications
(7) Drawings
(8) Bill of quantities and
(9) any other document listed in the Contract Data as forming part of the Contract.

3. Law governing contract

The law governing the Contract is the Laws of India supplanted by the Karnataka Local Acts.

4. Employer's decisions

Except where otherwise specifically stated, the Employer will decide contractual matters between the Employer and the Contractor.

5. Delegation

The Employer may delegate any of his duties and responsibilities to other people after notifying the Contractor and may cancel any delegation after notifying the Contractor.

6. Communications

Communications between parties which are referred to in the conditions are effective only when in writing. A notice shall be effective only when it is delivered (in terms of Indian Contract Act).

7. Subcontracting (Deleted)

Deleted.

8. Other Contractors

The Contractor shall cooperate and share the Site with other contractors, public authorities, utilities, and the Employer.

9. Personnel

The Contractor shall employ the technical personnel (of number and qualifications) as may be stipulated by GOK from time to time during the execution of the work. The technical staff so employed shall be available at site as may be stipulated by the Employer.
If the Employer asks the Contractor to remove a person who is a member of the Contractor's staff or his work force stating the reasons, the Contractor shall ensure that the person leaves the Site within seven days and has no further connection with the work in the Contract.

10. Employer's and Contractor's risks

The Employer carries the risks which this Contract states are Employer's risks, and the Contractor carries the risks which this Contract states are Contractor's risks.

11. Employer's risks

The Employer is responsible for the excepted risks which are:

(a) rebellion, riot commotion or disorder unless solely restricted to employees of the Contractor or his Sub-Contractors arising from the conduct of the Works; or

(b) a cause due solely to the design of the Works, other than the Contractor's design; or

(c) any operation of the forces of nature (in so far as it occurs on the Site) which an experienced contractor:

- (i) could not have reasonably foreseen; or
- (ii) could reasonably have foreseen, but against which he could not reasonably have taken at least one of the following measures;

(A) prevent loss or damage to physical property from occurring by taking appropriate measures or
(B) insure against such loss or damage

12. Contractor's risks

All risks of loss of or damage to physical property and of personal injury and death which arise during and in consequence of the performance of the Contract other than the excepted risks are the responsibility of the Contractor.

13. Insurance:

The Contractor shall prior to commencing the works, effect and thereafter maintain insurances , in the joint names of the Employer and the Contractor, (cover from the first working day after the Start Date to the end of Defects Liability Period), in the amounts stated in the Contract Data :

(a) for loss of or damage to the Works, Plants and Materials and the Contractor's equipment;
(b) for liability of both Parties for loss, damage, death and injury to third parties or their property arising out of the Contractor's performance of the Contract including the Contractor's liability for damage to the Employer's property other than the Works and
(c) for liability of both Parties and of any Employer's representative for death and injury to the Contractor's personnel except to the extent that liability arises from the negligence of the Employer, any Employer's representative or their Employees.

Policies and certificates for insurance shall be delivered by the Contractor to the Employer for his approval before the Start Date. All such insurance shall provide for compensation to be payable to rectify the loss or damage incurred. All payments received from insurers relating to loss or damage shall be held jointly by the Parties and used for the repair of the loss or damage or as compensation for loss or damage that is not to be repaired.

If the Contractor fails to effect or keep in force any of the insurances referred to in the previous sub-clauses or fails to provide satisfactory evidence, policies or receipts, the Employer may without prejudice to any other right or remedy, effect insurance for the cover relevant to such default and pay the premiums due and recover the same as a deduction from any other monies due to the Contractor. If no payments is due, the payment of the premiums shall be a debt due.

Alterations to the terms of an insurance shall not be made without the approval of the Employer.

Both Parties shall comply with any conditions of the insurance policies.

14. Site Investigation Reports:

The Contractor, in preparing the tender, shall rely on any site investigation

reports referred to in the Contract data, supplemented by any information available to the Tenderer.

15. Queries about the Contract Data

The Employer will clarify queries on the Contract Data.

16. Contractor to construct the Works

The Contractor shall construct the Works in accordance with the Specification and Drawings.

17. The Works to be completed by the Intended Completion Date

The Contractor may commence execution of the Works on the Start Date and shall carry out the Works in accordance with the program submitted by the Contractor, as updated with the approval of the Employer, and complete them by the Intended Completion Date.

18. Approval by the Employer:

The Contractor shall submit Specification and drawings showing the proposed Temporary Works to the Employer, who is to approve them if they comply with the Specifications and Drawings.

The Contractor shall be responsible for the design of Temporary Works

The Employer's approval shall not alter the Contractor's responsibility for design of the Temporary Works.

The Contractor shall obtain approval of third parties to the design of third parties to the design of the temporary Works where required.

All Drawings prepared by the Contractor for the execution of the temporary or permanent Works, are subject to prior approval by the Employer before their use.

19. Safety

The Contractor shall be responsible for the safety of all activities on the Site.

20. Discoveries

20..1 Anything of historical or other interest or of significant value unexpectedly discovered on the Site is the property of the Employer. The Contractor is to notify the Employer of such discoveries and carry out the Employer's instructions for dealing with them.

21. Possession of the Site

The Employer shall give possession of all parts of the Site to the Contractor.

If possession of a part is not given by the date stated in the Contract Data the Employer is deemed to have delayed the start of the relevant activities and this will be Compensation Event.

22. Access to the Site

The Contractor shall allow the Employer and any person authorized by the Employer access to the Site, to any place where work in connection with the Contract is being carried out or is intended to be carried out and to any place where materials or plant are being manufactured / fabricated / assembled for the works.

23. Instructions

The Contractor shall carry out all instructions of the Employer which comply with the applicable laws where the Site is located.

24. Procedure for resolution of Disputes:

If the Contractor is not satisfied with the decision taken by the Employer, the dispute shall be referred by either party to Arbitration within 30 days of the notification of the Employer's decision.
If neither party refers the dispute to Arbitration within the above 30 days, the Employer's decision will be final and binding.
The Arbitration shall be conducted in accordance with the arbitration procedure stated in the Special Conditions of Contract.

B. Time Control

25. Program

Within the time stated in the Contract Data the Contractor shall submit to the Employer for approval a Program showing the general methods, arrangements, order, and timing for all the activities in the Works.
The Employer's approval of the Program shall not alter the Contractor's obligations. The Contractor may revise the Program and submit it to the Employer again at any time. A revised Program is to show the effect of Variations and Compensation Events.

26. Extension of the Intended Completion Date

The Employer shall extend the Intended Completion Date if a Compensation Event occurs or a Variation is issued which makes it impossible for Completion to be achieved by the Intended Completion Date.
The Employer shall decide whether and by how much to extend the Intended Completion Date within 21 days of the Contractor asking the Employer for a decision upon the effect of a Compensation Event or Variation and submitting full supporting information.

27. Delays ordered by the Employer

The Employer may instruct the Contractor to delay the start or progress of any activity within the Works.

28. Management meetings

The Employer may require the Contractor to attend a management meeting. The business of a management meeting shall be to review the progress achieved and the plans for remaining work.
The responsibility of the parties for actions to be taken is to be decided by the Employer either at the management meeting or after the management meeting and stated in writing to be distributed to all who attended the meeting.

C. Quality Control

29. Identifying defects

The Employer shall check the Contractor's work and notify the Contractor of any Defects that are found. Such checking shall not affect the Contractor's responsibilities. The Employer may instruct the Contractor to search for a Defect and to uncover and test any work that the Employer considers may have a Defect

30. Tests

If the Employer instructs the Contractor to carry out a test not specified in the Specification to check whether any work has a Defect and the test shows that it does, the Contractor shall pay for the test and any samples. If there is no Defect the test shall be a Compensation Event.

31. Correction of defects

The Employer shall give notice to the Contractor of any Defects before the end of the Defects Liability Period, which begins at Completion and is defined in the Contract Data. The Defects Liability Period shall be extended for as long as Defects remain to be corrected.
Every time notice of a Defect is given, the Contractor shall correct the notified Defect within the length of time specified by the Employer’s notice.

32. Uncorrected defects

If the Contractor has not corrected a Defect within the time specified in the Employer’s notice, the Employer will assess the cost of having the Defect corrected, and the Contractor will pay this amount.

D. Cost Control

33. Bill of Quantities (BOQ)

The BOQ shall contain items for the construction, installation, testing, and commissioning work to be done by the Contractor.
The BOQ is used to calculate the Contract Price. The Contractor is paid for the quantity of the work done at the rate in the BOQ for each item

34. Variations

The Employer shall have power to order the Contractor to do any or all of the following as considered necessary or advisable during the progress of the work by him

(a) Increase or decrease of any item of work included in the Bill of Quantities (BOQ);
(b) Omit any item of work;
(c) Change the character or quality or kind of any item of work;
(d) Change the levels, lines, positions and dimensions of any part of the work;
(e) Execute additional items of work of any kind necessary for the completion of the works; and
(f) Change in any specified sequence, methods or timing of construction of any part of the work.

The Contractor shall be bound to carry out the work in accordance with any instructions in this connection, which may be given to him in writing by the Employer and such alteration shall not vitiate or invalidate the contract.

Variations shall not be made by the Contractor without an order in writing by the Employer, provided that no order in writing shall be required for increase or decrease in the quantity of an item appearing in the BOQ so long as the work executed conforms to the approved drawings.
The Contractor shall promptly request in writing to the Employer to confirm verbal orders and the officer issuing oral instructions shall confirm it in writing within 30 days, failing which the work shall be carried out as though there is no variation. In case variation is approved it shall be accompanied by BOQ, failing which the contractor shall be responsible for deviation if any. Further, approval of Govt. / BSWML has to be obtained for the variation exceeding 5%.

35. Payments for Variations

Payment for increase in the quantities of an item in the BOQ up to 25% of that provided in the Bill of Quantities shall be made at the rates quoted by the Contractor.
For quantities in excess of 125% of the tendered quantity of an item as given in the BOQ, the Contractor shall be paid at the rate entered in or derived from in the Schedule of Rates (applicable for the area of the work

and current at the time of award of contract) plus or minus the overall percentage of the original tendered rates over the current Schedule of Rates prevalent at the time of award of contract.
If there is no rate for the additional, substituted or altered item of the work in the BOQ, efforts would be made to derive the rates from those given in the BOQ or the Schedule of Rates (applicable for the area of the work and current at the time of award of contract) and if found feasible the payment would be made at the derived rate for the item plus or minus the overall percentage of the original tendered rates over the current Schedule of Rates prevalent at the time of award of contract
If the rates for additional, substituted or altered item of work cannot be determined either as at 35.1 or 35.2 or 35.3 above, the Contractor shall be requested to submit his quotation for the items supported by analysis of the rate or rates claimed, within 7 days.
If the Contractor's quotation is determined unreasonable, the Employer may order the Variation and make a change to the Contract Price which shall be based on Employer's own forecast of the effects of the Variation on the Contractor's costs.

If the Employer decides that the urgency of varying the work would prevent a quotation being given and considered without delaying the work, no quotation shall be given and the Variation shall be treated as a Compensation Event.
Under no circumstances the Contractor shall suspend the work on the plea of non-settlement of rates for items falling under this Clause.

36. Submission of bills for payment

The Contractor shall submit to the Employer monthly bills of the value of the work completed less the cumulative amount paid previously.
The Employer shall check the Contractor's bill and determine the value of the work executed which shall comprise of (i) value of the quantities of the items in the BOQ completed and (ii) valuation of Variations and Compensation Events.
The Employer may exclude any item paid in a previous bill or reduce the proportion of any item previously paid in the light of later information.

37. Payments

Payments shall be adjusted for deductions for advance payments other than recoveries in terms of contract and taxes, at source, as applicable under the law. The Employer as far as possible shall pay the Contractor the within 60 days of submission of bill. The contractor shall be liable to pay liquidated damages for shortfall in progress. For progress beyond the agreed programmer payment is subject to availability of the grants.
Items of the Works for which no rate or price has been entered in will not

be paid for by the Employer and shall be deemed covered by other rates and prices in the Contract.

38. Compensation events

The following are Compensation events unless they are caused by the Contractor:

(a) The Employer does not give access to a part of the Site by the Site Possession Date stated in the Contract Data.
(b) The Employer orders a delay or does not issue drawings, specifications or instructions required for execution of works on time.
(c) The Employer instructs the Contractor to uncover or to carry out additional tests upon work which is then found to have no Defects.
(d) The Employer gives an instruction for dealing with an unforeseen condition, caused by the Employer, or additional work required for safety or other reasons.
(e) The effect on the Contractor of any of the Employer's Risks.
(f) The Employer unreasonably delays issuing a Certificate of Completion.
(g) Other Compensation Events listed in the Contract Data or mentioned in the Contract.

If a Compensation Event would cause additional cost or would prevent the work being completed before the Intended Completion Date, the Contract Price shall be increased and/or the Intended Completion Date is extended. The Employer shall decide whether and by how much the Contract Price shall be increased and whether and by how much the Intended Completion Date shall be extended.

As soon as information demonstrating the effect of each Compensation event upon the Contractor's forecast cost has been provided by the Contractor, it is to be assessed by the Employer and the Contract Price shall be adjusted accordingly. If the Contractor's forecast is deemed unreasonable, the Employer shall adjust the Contract Price based on Employer's own forecast. The Employer will assume that the Contractor will react competently and promptly to the event.
The Contractor shall not be entitled to compensation to the extent that the Employer's interests are adversely affected by the Contractor not having given early warning or not having cooperated with the Employer.

39. Tax

The rates quoted by the Contractor shall be deemed to be exclusive of GST and inclusive of other taxes that the Contractor will have to pay for the performance of this Contract. The Employer will perform such duties in regard to the deduction of such taxes at source as per applicable law.

40. Price Adjustment: Refer Section 6: Contract Data

41. Liquidated damages:

The Contractor shall pay liquidated damages to the Employer at the rate per day stated in the Contract Data for each day that the Completion Date is later than the Intended Completion Date (for the whole of the works or the milestone as stated in the Contract Data). The total amount of liquidated damages shall not exceed the amount defined in the Contract Data. The Employer may deduct liquidated damages from payments due to the Contractor. Payment of liquidated damages does not affect the Contractor's liabilities.
If the Intended Completion Date is extended after liquidated damages have been paid, the Employer shall correct any overpayment of liquidated damages by the Contractor by adjusting the next payment of bill.

42. Advance Payments: Refer Section 6: Contract Data

43. Securities:

The Security deposit (including additional security for unbalanced tenders) shall be provided to the Employer no later than the date specified in the Letter of Acceptance and shall be issued in an amount and form and type of instrument acceptable to the Employer. The Security deposit shall be valid until a date 30 days from the date of

expiry of Defects Liability Period and the additional security for unbalanced tenders shall be valid until a date 30 days from the date of issue of the certificate of completion.

44. Cost of Repairs:

Loss or damage to the Works or Materials to be incorporated in the Works between the Start Date and the end of the Defects Correction periods shall be remedied by the Contractor at the Contractor's cost if the loss or damage arises from the Contractor's acts or omissions.

E. Finishing the Contract

45. Completion

The Contractor shall request the Employer to issue a Certificate of Completion of the Works and the Employer will do so upon deciding that the Work is completed.

46. Taking over

The Employer shall take over the Site and the Works within seven days of issuing a certificate

of Completion.

47. Final account

The Contractor shall supply to the Employer a detailed account of the total amount that the Contractor considers payable under the Contract before the end of the Defects Liability Period. The Employer shall issue a Defect Liability Certificate and certify any final payment that is due to the Contractor within 90 days of receiving the Contractor's account if it is correct and complete. If it is not, the Employer shall issue within 90 days a schedule that states the scope of the corrections or additions that are necessary. If the Final Account is still unsatisfactory after it has been resubmitted, the Employer shall decide on the amount payable to the Contractor and make payment within 60 days of receiving the Contractor's revised account.

48. As built drawings and /or Operating and Maintenance Manuals

If "as built" (*Completion drawings*) Drawings and/or operating and maintenance manuals are required, the Contractor shall supply them by the dates stated in the Contract Data.

If the Contractor does not supply the Drawings by the dates stated in the Contract Data, or they do not receive the Employer's approval, the Employer shall withhold the amount stated in the Contract Data from payments due to the Contractor.

49. Termination

The Employer may terminate the Contract if the other party causes a fundamental breach of the Contract.

Fundamental breaches of Contract include, but shall not be limited to the following:

(a) the Contractor stops work for 45 days when no stoppage of work is shown on the current Program and the stoppage has not been authorized by the Employer;
(b) Deleted.
(c) The Contractor becomes bankrupt or goes into liquidation other than for a reconstruction or amalgamation;
(d) Deleted.
(e) the Employer gives Notice that failure to correct a particular Defect is a fundamental breach of Contract and the Contractor fails to correct it within a reasonable period of time determined by the Employer;
(f) the Contractor does not maintain a security which is required;
(g) the Contractor has delayed the completion of works by the number of days for which the maximum number of liquidated damages can be paid as defined in the Contract data; and

(h) if the Contractor, in the judgment of the Employer has engaged in corrupt or fraudulent practices in competing for or in the executing the Contract.

For the purpose of this paragraph: “corrupt practice” means the offering, giving, receiving or soliciting of anything of value to influence the action of a public official in the procurement process or in contract execution. “Fraudulent practice” means a misrepresentation of facts in order to influence a procurement process or the execution of a contract to the detriment of the Borrower, and includes collusive practice among Tenderers (prior to or after Tender submission) designed to establish Tender prices at artificial non-competitive levels and to deprive the Borrower of the benefits of free and open competition.”

When either party to the Contract gives notice of a breach of contract to the Employer for a cause other than those listed under Sub Clause 49.2 above, the Employer shall decide whether the breach is fundamental or not.

Notwithstanding the above, the Employer may terminate the Contract for convenience.

If the Contract is terminated the Contractor shall stop work immediately, make the Site safe and secure and leave the Site as soon as reasonably possible.

50. Payment upon Termination

If the Contract is terminated because of a fundamental breach of Contract by the Contractor, the Employer shall prepare bill for the value of the work done less advance payments received up to the date of the bill, less other recoveries due in terms of the contract, less taxes due to be deducted at source as per applicable law and less the percentage to apply to the work not completed as indicated in the Contract Data. Additional Liquidated Damages shall not apply. If the total amount due to the Employer exceeds any payment due to the Contractor the difference shall be a debt payable to the Employer.

If the Contract is terminated at the Employer's convenience or because of a fundamental breach of Contract by the Employer, the Employer shall prepare bill for the value of the work done, the reasonable cost of removal of Equipment, repatriation of the Contractor's personnel employed solely on the Works, and the Contractor's costs of protecting and securing the Works and less advance payments received up to the date of the certificate, less other recoveries due in terms of the contract, and less taxes due to be deducted at source as per applicable law and make payment accordingly.

51. Property

All materials on the Site, Plant, Equipment, Temporary Works and Works are deemed to be the property of the Employer, if the Contract is terminated because of a Contractor's default.

52. Release from performance

If the Contract is frustrated by any event entirely outside the control of either the Employer or the Contractor the Employer shall certify that the Contract has been frustrated. The Contractor shall make the Site safe and stop work as quickly as possible after receiving this certificate and shall be paid for all work carried out before receiving it and for any work carried out afterwards to which commitment was made

F. Special Conditions of Contract

1. Labour :

The Contractor shall, unless otherwise provided in the Contract, make his own arrangements for the engagement of all staff and labour, local or other, and for their payment, housing, feeding and transport.

The Contractor shall, if required by the Employer, deliver to the Employer a return in detail, in such form and at such intervals as the Employer may prescribe, showing the staff and the numbers of the several classes of labour from time to time employed by the Contractor on the Site and such other information as the Employer may require.

2. Compliance with labour regulations:

During continuance of the contract, the Contractor shall abide at all times by all existing labour enactments and rules made there under, regulations, notifications and bye laws of the State or Central Government or local authority and any other labour law (including rules), regulations, bye laws that may be passed or notification that may be issued under any labour law in future either by the State or the Central Government or the local authority. The Contractor shall keep the Employer indemnified in case any action is taken against the Employer by the competent authority on account of contravention of any of the provisions of any Act or rules made there under, regulations or notifications including amendments. If the Employer is caused to pay or reimburse, such amounts as may be necessary to cause or observe, or for non-observance of the provisions stipulated in the notifications/bye laws/Acts/Rules/regulations including amendments, if any, on the part of the Contractor, Employer shall have the right to deduct any money due to the Contractor including his amount of security deposit. The Employer shall also have right to recover from the Contractor any sum

required or estimated to be required for making good the loss or damage suffered by the Employer.

The employees of the Contractor in no case shall be treated as the employees of the Employer at any point of time.

3. Protection of Environment:

The contractor shall take all reasonable steps to protect the environment on and off the Site and to avoid damage or nuisance to persons or to property of the public or others resulting from pollution, noise or other causes arising as a consequence of his methods of operation. During continuance of the contract, the contractor shall abide at all times by all existing enactments on environmental protection and rules made there under, regulations, notifications and bye-laws of the State or Central Government, or local authorities and any other law, bye-law, regulations that may be passed or notification that may be issued in this respect in future by the State or Central Government or the local authority.

4. Arbitration (Clause 24): Deleted

5. In the case of the death of a Contractor after executing the agreement / commencement of the work, his legal heir, if an eligible registered Contractor and willing can execute and complete the work at the accepted tender rates irrespective of the cost of the work.

6. The Contractor shall provide One four-wheeler along with driver, fuel expenses to Project Engineers in-charge of work to facilitate and co-ordinate the supervision of the work.

7. The Contractor shall establish field lab and field office to facilitate quality assurance of execution of works.

Annexure:

LIST OF ORGANIZATIONS WHO ARE CONSIDERED AS APPOINTING AUTHORITY FOR APPOINTMENT OF ARBITRATORS

1. Indian Council of Arbitration, New Delhi;
2. International Centre for Alternative Disputes Resolution (India);
3. Indian Roads Congress;
4. Indian Building Congress;
5. Indian Institute of Bridge Engineers;
6. Indian Institute of Public Health Engineers;
7. Institute of Water Works

SECTION 6: CONTRACT DATA

Items marked "N/A" do not apply in this Contract.

The following documents are also part of the Contract: **Clause Reference**

- The Schedule of Operations Manuals [48]
- The Methodology and Program of Construction [25]
- Site Investigation Reports [14]
- The Schedule of Key and Critical Equipment to be deployed on the work as per agreed program of construction.

[25] The Employer is:

Name: **The Managing Director** [1.1]
BSWML, Bangalore

Name of authorized Representative:
Office of the Deputy General
Manager-3, BSWML, 1st Floor,
GBA Building,
Thimmaiah road, Bengaluru-560051

The name and identification number of the Contract is **DGM-3/BSWML/TEND/26/2025-26, Date:16.03.2026** [1.1]

"**Bio-Enzyme based Odour Suppression and Basic infrastructure development works in and around MSGP processing plants in Doddaballapura Constituency**"

The Works consist of Earthwork excavation, Providing PCC, TMT Steel, 100mm precast covering slab, GSB, WMM, DBM, BC, DLC, Concrete and Spraying of lemon grass.

The start date shall be the date of issue of notice to proceed with the work. [1.1]

The Intended Completion Date for the whole of the Works is **09 months** with the following milestones [17, 26]

The Defects Liability Period: 12 Months

The Site Possession Date is: Date of work order [21]

The Site is located at **Doddaballapura constituency** [1.1]

"Bio-Enzyme based Odour Suppression and Basic infrastructure development works in and around MSGP processing plants in Doddaballapura Constituency"

Insurance requirements are as under:

	Type of Cover	Minimum cover for Insurance[6]
(i)	Works and of Plant and materials	The sum stated in the Agreement (contract Value) plus 20%
(ii)	Loss or damage to equipment	Full replacement cost
(iii)	Loss or damage to property of Third Party	Full replacement cost
(iv)	Personal injury or death insurance (a) for Third Party[7]	5.00 Lakhs each person
	(b) for Contractor's employees or labour	In accordance with the statutory requirements applicable to Karnataka Rs. 5.00Lakhs each person

Price Adjustment: Deleted

The liquidated damages for the whole of the works are Rs.82,374.16 (amount) per day and that for the Milestones are as under:

For Milestone 1:	Rs. 27,458.00 per day
For Milestone 2:	Rs. 27,458.00 per day
For Milestone 3:	Rs. 27,458.00 per day

The maximum amount of liquidated damages for the whole of the works

[41] is Ten percent of final contract price.

The amounts of the advance payment are NIL [42]

SECTION 7: SPECIFICATIONS

(ENCLOSED)

SECTION 8: DRAWINGS

As per approved DPR

BILL OF QUANTITIES

SI No	Description of Item	Unit	Estimate Quantity	Estimate Rate in Rs.	Rate quoted by contractor in Figures in Rs.	Rate quoted by contractor in words
1	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, including removal and disposal of top organic soil not exceeding 150 mm in thickness.By (ii) Mechanical Means using Dozer b) In area of thorny jungle 100 m2 as per the direction of engineer in charge of work	per 100 sqm	207.60	498.52		
2	Earth work excavation for Foundation by mechanical means for all works & depth upto 3 m, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenaces required to complete the work In all kinds of soils Depth upto 3 m as per the direction of engineer in charge of work	Cum	5185.88	105.06		
3	Earth work in surface excavation by mechanical means for lowering & leveling the ground for all works other than foundation in all kinds of soils & upto depth not exceeding 300mm as per drawing and	Cum	3043.86	97.85		

	technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work.In all kinds of soils upto 300 mm depth as per the direction of engineer in charge of work					
4	Preparation and surface treatment of formation by removing mud and slurry, watering to the extent needed to maintain the desired moisture content, trimming to the required line, grade, profile and rolling with 8-10 t smooth wheeled roller, complete as per clause 301. as per the direction of engineer in charge of work	Sqm	10146.20	4.12		
5	Construction of Granular Sub-Base of required grading as per design mixing in a mechanical mix plant at OMC, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per clause 401 (v) For Grading -V Material as per the direction of engineer in charge of work	Cum	1428.51	2561.61		
6	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in	Cum	843.90	2635.77		

	sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density.as per the direction of engineer in charge of work					
7	Prime Coat over WMM/WBM Providing and applying primer coat with SS1 grade Bitumen Emulsion on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70 kg/m2 using mechanical means.as per the direction of engineer in charge of work	Sqm	2910.00	47.38		
8	Providing and laying Dense Graded Bituminous Macadam with 40/60 TPH capacity HMP using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 4.5 per cent by weight of total mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 505 complete in all respects. Dense Graded Bituminous macadam Grading - ii for traffic <20 mSa as per the direction of engineer in charge of work	Cum	145.50	10515.27		
9	Tack coat on Bituminous surface Providing and applying tack coat with RS1 Bituminous Emulsion using emulsion pressure distributor at the rate of 0.20 kg/m2 on the prepared bituminous surface cleaned with mechanical broom as per the direction of engineer in charge of work	Sqm	2910.00	13.39		
10	Providing and laying Bituminous Concrete with 40/60 TPH capacity hot mix plant using crushed	Cum	116.40	12243.61		

	aggregates of specified grading, premixed with bituminous binder VG-30, @ 5.4 per cent of mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 507 complete in all respects B)Bituminous Concrete Grading ii for traffic <20 mSa as per the direction of engineer in charge of work					
11	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 g/m2 area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35:2015.The finished surface to be level,uniform and free from streaks and holes.as per the direction of engineer in charge of work	Sqm	155.20	545.90		
12	Construction of Embankment by excavating the available approved Gravel/Murrum deposited at a place or borrow pits during or prior excavation with all lifts and lead, transportation to site, spreading, grading to required slope and compacting to meet the requirement complete as per specifications, including cost of labour,rolling,water,all materials,usage& all other appurtenaces required to complete the work.as per the direction of engineer in charge of work	Cum	1123.37	488.22		
13	Construction of dry lean cement concrete Sub- base over a prepared	Cum	828.75	5716.00		

	sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 14:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 140 kg/ m3 , optimum moisture content to be determined during trial length construction, concrete strength not to be less than 7 Mpa at 7 days, mixed in a batching plant, transported to site spreading in unifrom layers by manual means compacting with 8-10 tonne vibratory rollar finishing and curing as per the direction of engineer in charge of work					
14	Construction of M30 Grade un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with OPC @ 270 kg/m3 and GGBS@ 90 kg/m3, coarse and fine aggregate conforming to IS 383:2016, maximum size of coarse aggregate not exceeding 25 mm, mixed in a batching and mixing plant as per approved mix design transported to site, laid with a paver finisher, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation Pavement Quality M30 grade Concrete (RMC) with OPC & GGBS laid using Paver membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures, curing compound, steel channels, finishing to lines and grades as per drawing.as per the direction of engineer in charge of work	Cum	731.25	7633.33		
15	Loading and Unloading of Stone Boulder/Stone	Cum	8229.74	88.58		

	aggregates/Sand/Kankar/Moorum. (Tipper 14 m3) as per the direction of engineer in charge of work					
16	Cost of Haulage Excluding Loading and Unloading Case-1 : Surfaced Road Taking output 25 tonnes load and lead 10 km = 250 t.km as per the direction of engineer in charge of work	t.km	105340.67	7.21		
17	Supplying Preparation And Spraying of Lemon Grass Supplying preparation and spraying of lemon grass to reduce foul labors and control in pets including cost of materials and labours for preparation spraying supervision HOM on water tanker fuel charges and crew charges loading unloading transportation labours charges incidental charges etc. complete and with all lead and lift loading and unloading as per the direction of engineer in charge of work	Ltr	440000.00	35.00		
18	Supplying of Pyctrum/ King Fog Etc Supplying of pyetrum/ king Fog etc, (contains detamethrine 1.25%) by thermal fogging to control mosquito meance including all lead and lift charges as per the direction of engineer in charges	Ltr	88.00	5350.00		
19	Supply Mixing of Diesel With Chemical Supply mixing of diesel with chemical in required ratio with diesel and petrol in the fogging machine -10 liter/day including all lead and lift charges as per the direction of engineer in charges	Set	924.00	150.00		
20	Earth work in surface excavation by manual means for lowering & levelling the ground by chiselling and wedging in Hard rock for all works other than foundation & depth not exceeding 100 mm as per drawing and technical specifications, including setting out, barricading, caution lights,	Sqm	61.88	182.31		

	dressing of excavated surfaces, disposing off the excavated spalls/stuff & stacking the selected spall/ stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage & other appurtenances required to complete the work.as per the direction of engineer in charge of work					
21	Earth work excavation by manual means for drains, canals, waste weir, draft, approach channels, key trenches, foundation of Buildings & bridges and such simillar works in all kinds of soils, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work.Depth exceeding 1.5m, but not exceeding 3 m as per the direction of engineer in charge of work	Cum	76.56	266.77		
22	Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical	Cum	65.38	6095.54		

	specifications.Mix 1:3:6 Using 40 mm nominal size graded crushed coarse aggregates as per the direction of engineer in charge of work					
23	Providing Coursed rubble masonry (first sort) with hard stone in foundation and plinth with Cement mortar 1:6 (1 cement : 6 coarse sand)as per the direction of engineer in charge of work	Cum	50.11	6791.82		
24	Providing Coursed rubble masonry (second sort) with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement : 6 coarse sand)as per the direction of engineer in charge of work	Cum	33.41	6366.43		
25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations and other similar works etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.as per the direction of engineer in charge of work	Cum	119.07	273.98		
26	Providing and laying in position Cement Concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical	Cum	39.92	10404.03		

	specifications. M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates as per the direction of engineer in charge of work- **RCC Roof Slabs** & **Plinth Beams of Buildings**					
27	Providing and laying in position Cement Concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates as per the direction of engineer in charge of work**- For Roof beams & Lintels**	Cum	16.98	11097.63		
28	Providing and laying in position Cement Concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage	Cum	1.84	10057.23		

	charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates as per the direction of engineer in charge of work **- Chejjas.**					
29	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x150x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete aas per the direction of engineer in charge of works per specifications.	Sqm	378.48	1265.87		
30	Supplying, fitting and placing TMT FE 550 / 550D Steel Reinforcement including cost of all materials, machinery, labour, cleaning, straightening, cutting, bending, hooking, laping/welding joints, tying with binding wire / soft annealed steel wire and other ancilary operations complete as per drawing and technical specification .a. Buildings as per the direction of engineer in charge of work	Tonnes	75.58	82600.85		
31	Providing & fixing of 2-track x 2-panel sliding windows made out of multi chambered UPVC(Matching to RAL-9016) sections and with minimum TiO2(Titanium Dioxide) at 6 PHR with TPE (Thermo Plastic Elastomer) and lead free, gaskets - grey color having isolated drainage and reinforced with Galvanized Iron profile through-out the window frame. The outer frame having an overall size of 44mm width x	Sqm	46.08	5173.69		

	40mmheight with reinforcement of 1mm thickness and Sash with overall size of 27mm X 53mm with UPVC honeycomb structure inside in lieu of GI reinforcement. Coextruded Glazing bead for fixing of glass shall be of size 9.5mm x 21.5mm. Windows shall be provided with 5mm plain float glass, standard hardware& single point locking system with Crescent Locks. Wall thickness of frame & sash shall be of 2 mm. Maximum possible size – 1219mm x 1219mm. (The cost is inclusive of all fixtures and separate charges for minor T&P's shall not be made)as per the direction of engineer in charge of work					
32	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to openings /wooden frames with rawl plugs screws etc.as per the direction of engineer in charge of work	Kg	1612.80	188.49		
33	Providing 12 mm cement plaster with Cement mortar 1:3 (1 cement: 3 coarse sand) finished with a floating coat of neat cement to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer in-charge.as per the direction of engineer in charge of work	Sqm	164.92	332.69		
34	Providing 15 mm cement plaster with cement mortar 1:3 (1 cement: 3 coarse sand) finished with a floating coat of neat cement on the	Sqm	76.64	372.86		

	rough side of single or half brick wall including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.					
35	Providing 15 mm cement plaster on rough side of single or half brick wall finished with a floating coat of neat cement of mix 1:3 (1 cement: 3 fine sand)including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	528.84	357.41		
36	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg/m2, including pointing in white cement mixed with pigment of matching shade complete.as per the direction of engineer in charge of work	Sqm	528.84	1139.18		
37	Providing 18 mm cement plaster in two coats under layer 12 mm thick cement plaster with cement mortar 1:5 (1 cement : 5 coarse sand)finished with a top layer 6 mm thick cement plaster with cement mortar 1:6 (1 cement : 6 fine sand) to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding,	Sqm	579.72	380.07		

	including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.					
38	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per specifications and as per directions of Engineer in charge.	Sqm	1962.68	103.00		
39	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications: Two coats applied on walls @ 1.25 L/10 m^2 over and including one coat of Special primer applied @ 0.75 L/10 m^2 with paint of approved quality to give an even shade, after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (The gloss should be 50% @ 60 degree angle with 10 years life)as per the direction of engineer in charge of work	Sqm	622.70	162.74		
40	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade :New work (two coats) over and in cluding water thinnable priming coat with cement primer after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions	Sqm	1339.98	141.11		

	of Engineer-in-charge.					
41	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives with pure Acrylic Resin, UV resistant, dirt & pick up resistant, Alkali & Water resistant of required shade: New work (Two coats applied @ 1.43 L/10 m^2 over and including priming coat of exterior primer applied @ 2.20 kg/10 m^2) with paint of approved quality to give an even shade, after thoroughly brooming the surface to remove all dirt, dust,mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge	Sqm	4710.23	183.34		
42	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :Two coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	321.02	172.01		
43	Providing and laying vitrified floor tiles with thickness 9-10 mm in different sizes with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ m2 including grouting the joints with white	Sqm	121.00	1179.35		

	cement and matching pigments etc., complete Size of Tile 600x600 mm as per the direction of engineer in charge of work					
44	Integral Crystalline water proofing Admixture Providing and supplying crystalline integral concrete waterproofing admixture that waterproofs concrete by forming crystals deep in the pores, capillaries and microcracks of the concrete, self-seal waterproofing compound to bridge shrinkage cracks upto 0.5mm in width & resist hydro-static pressure upto 16bar for both positive & negative pressure confirming to DIN 1048 part 5 for 56% reduction in depth of penetration against control, resistance to chloride penetration confirming to ASTM C 1202 with 64% improvement against control & protecting steel reinforcement against corrosion mixed @ 1% by weight of cementitious content in concrete. ie., integral crystaline waterproofing admix @ 0.5 kg/bag of cement. (For calculation purpose 320 kg of Cement for M-20 grade of Concrete is considered in the analysis)as per the direction of engineer in charge of work	Cum	28.91	633.45		
45	Supplying and fixing rolling shutters of approved make, made of required size M.S.laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate	Sqm	99.84	2711.99		

	strength conforming to IS: 4454 - part 1 and M.S. top cover of required thickness for rolling shutters. 80x1.25 mm M.S. laths with 1.25 mm thick top cover including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.					
46	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate sections and other sections of approved make conforming to IS:733 and IS:1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle,Aluminium snap beading for glazing / paneling, C.P. brass/stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in charge. (Glazing, paneling and dash fasteners to be paid for separately) :For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Polyester powder coated aluminium (minimum thickness of polyester powder coating 50 micron) including cost of materials, labour, usage charges	Kg	998.40	599.46		

	of machinery complete as per specifications as per the direction of engineer in charge of work					
47	Supply, Installation & Commissioning of 500 LPH Capacity Water Purification Plant with 10" x 54" FRP Vessels 2 numbers - Sand & Carbon Media filter, SS tank of capacity 2000 ltrs for water storage including with stainless steel cabinet with meter display, 2 number Micron Filters, 0.5hp Feed pump, 3LPH Antiscalant Dosing Pump, 1.5hp High Pressure Pump, 4" x 40" RO membrane with frp housing 2 numbers, 25 watts UV Set, Coin Vending Machine, 0.25hp feed pump for smooth functioning of Coin Vending Machine including 2000 Litres Raw Water Tank (Syntex), all these shall confirm to BIS: 10500:2012 standards along with 1 Year Warranty including cost of Transportation, lead & lift, loading & unloading charges, Labour, Commissioning etc., any other incidental charges, but excluding cost of Electrical, Plumbing & Civil Work as per the direction of the engineer incharge of work.	Each	42.00	524322.00		
48	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work 25 mm nominal dia Pipes as per the direction of engineer in charge of work	M	240.00	304.88		
49	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes,	M	1175.00	491.31		

	having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work 40 mm nominal dia Pipes as per the direction of engineer in charge of work					
50	Supplying heavy gauge PVC conduit pipe ..... mmdia.....mm thick confirming to IS 2509 with suitable size bends, metal/PVC Junction boxes, adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fish wire wherever necessary 19/20 mm dia 2 mm thick as per the direction of engineer in charge of work	Mtr	160.00	69.00		
51	Supplying heavy gauge PVC conduit pipe ..... mmdia.....mm thick confirming to IS 2509 with suitable size bends, metal/PVC Junction boxes, adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures, run with 18SWG GI fish wire wherever necessary 25 mm dia 2 mm thick as per the direction of engineer in charge of work	Mtr	160.00	81.00		
52	Supplying and fixing sheet Metal box made out of 18 SWG sheet metal with necessary holes for cable/conduit entry as required with one coat of primer of approved make etc 200 x 200 x 65 mm as per	Each	48.00	348.00		

	the direction of engineer in charge of work					
53	Supplying and fixing PVC/metal conduit Deep junction box 25 mm deep Junction box as per the direction of engineer in charge of work	Each	80.00	56.00		
54	Supplying and fixing of PVC casing and capping on the wall or ceiling using necessary materials like bends, junction box,elbows, screws at an interval of 300 mm .... etc. as required.as per the direction of engineer in charge of work	Each	96.00	28.00		
55	Supplying and fixing of PVC casing and capping on the wall or ceiling using necessary materials like bends, junction box, elbows, screws at an interval of 300 mm .... etc. as required.as per the direction of engineer in charge of work	Each	96.00	35.00		
56	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments 2.5 mm2 as per the direction of engineer in charge of work	Mtr	976.00	42.00		
57	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments 4 mm2 as per the direction of engineer in charge of work	Mtr	488.00	63.00		
58	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing	Each	48.00	344.00		

	metal/PVC box 10-12 Module as per the direction of engineer in charge of work					
59	Supplying and fixing of modular switch & connected accessories on existing modular switch plate as per IS 3854 and IS 1293 6A One Way Switch as per the direction of engineer in charge of work	Each	336.00	102.00		
60	Supplying and fixing of modular switch & connected accessories on existing modular switch plate as per IS 3854 and IS 1293 32A DP Switch as per the direction of engineer in charge of work	Each	32.00	326.00		
61	Supplying and fixing of metal clad industrial plugs and sockets 2pole+earth 250V PLUG as per the direction of engineer in charge of work	No;s	48.00	387.76		
62	Supplying And fixing/replacing of 6/16/32A electrical accessories on existing switch board. 6A Pendant Holder as per the direction of engineer in charge of work	Each	64.00	71.00		
63	Supplying of .....feet -PVC Batten with integrated LED tube ....W with high quality diffuser with Life of 25000 burning hours & 70% lumen maintenance with CRI > 80. Power Input: 220-240V@ 50/60Hz & Power factor >0.9 along with CE approved. 2 years Warranty against any manufacturing defect working under standard electrical condition. LED light fitting 1 x 4' - 20/22 W as per the direction of engineer in charge of work	Each	64.00	690.00		
64	Supplying and wiring adopting loop system in existing PVCConduit /casing capping using 2x1.5Sqmm (Phase & Neutral) &1x1.0 sqmm (Earth wire) FRLS multi strand PVC insulatedcopper wire (confirming to IS-694: and latest amendments) with a 6Amps flush type SP control switch shall be fixed on the existing	Point	48.00	570.00		

	plastic sheet/ gang box, the other end of the wires shall be terminatedwith sufficient loose length in a wood/PVC round block. complete foreach outlet.Long point above 6Mtr upto 10Mtr from tapping point to out let via switch as per the direction of engineer in charge of work					
65	Pipe Grounding GI Grounding pipe, B - Class, 42 mm dia, 2.5 Mtr long, 3.2 mm thick with bolt, nut, GI Strips and washer complete Minimum Weight of GI Pipe: 7.3 Kg as per the direction of engineer in charge of work	No	16.00	743.00		
66	Good Quality well burnt Charcoal for grounding purposes packed in non returnable gunny bag of 30 Kg each as per the direction of engineer in charge of work	No	16.00	676.00		
67	Good Quality Salt for grounding purposes packed in 50 Kg gunny bag as per the direction of engineer in charge of work	Bag	16.00	310.00		
68	Rod type of earthing using 40 mm Dia, 3 Mtr long MS rod as ground rod, in earth pit of 300 mm width and 3300 mm depth and using 50x6 mm flat welded to ground rod as terminal & connected to equipment ground terminal using PVC Al wire as specified as per the direction of engineer in charge of work	No	16.00	2172.00		
69	Bentonite clay slurry for earthing in 50 Kg Bag as per the direction of engineer in charge of work	Bag	16.00	368.00		
70	Supplying & fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Typecurve, indicator ON/OFF, energy cross-3 withShort circuit breaking capacity of 10 Kand complete wiringas required confirming to IEC 60898 50-63 A TPN as per the direction of engineer in charge of work	Each	32.00	3088.00		

71	Supply, Installation & Commissioning of Water Purification Plant of discharge capacity 50LPH with in-built SS 304 Grade Tank of 100 Ltrs capacity, 3 Numbers Faucets With Tray, Drain System & 20Ltr Can Filling arrangement System, water treatment using RO+UV+UF technology with 300 GPD RO Membrane - 1 No., 75 GPD RO Membrane - 1 No., Flow Restrictor Tube 450mm - 2nos, 600 GPD Booster Pump -1 No., Micron Filters - 2 Nos, Sediment Filter - 1 No., Ultrafiltration - 1 No., 11 Watts UV Set 1 No., , Alkaline / Mineral Filter - 1 No to enhance taste of water, all these should confirm with BIS 10500:2012 standards, Quality of product to be maintained as per ISO Standard 9001: 2015 and comply with Food & Safety Standard as per ISO 22000:2018 including cost of Transportation, lead & lift, loading & unloading charges, Labour, Commissioning etc., any other incidental charges, but excluding cost of Electrical, Plumbing & Civil Work as per the direction of the engineer incharge of work.	Each	57.00	143220.00		
72	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls	M	627.00	318.27		

	etc 25 mm nominal dia pipes 13.32.1 15 mm nominal dia pipes as per the direction of engineer in charge of work					

SECTION 10: FORMAT OF BANK GUARANTEE FOR SECURITY DEPOSIT

To:.....*[Name of Employer]*
..... *[address of Employer]*

WHEREAS ..... *[Name and address of Contractor]* (Hereinafter called "the Contractor") has undertaken, in pursuance of Contract No. ..... dated: ..... to execute .....*[name of Contract and brief description of Works]* (hereinafter called "the Contract");

AND WHEREAS it has been stipulated by you in the said Contract that the Contractor shall furnish you with a Bank Guarantee by a recognized bank for the sum specified therein as security for compliance with his obligations in accordance with the Contract;

AND WHEREAS we have agreed to give the Contractor such a Bank Guarantee;

NOW THEREFORE we hereby affirm that we are the Guarantor and responsible to you, on behalf of the Contractor, up to a total of Rs..... *[Amount of guarantee]*
[13]_Rupees.....0.....*[in words]*, and we undertake to pay you, upon your first written demand and without cavil or argument, any sum or sums within the limits of ..... *[Amount of guarantee]*[14] as aforesaid without your needing to prove or to show grounds or reasons for your demand for the sum specified therein.

We hereby waive the necessity of your demanding the said debt from the Contractor before presenting us with the demand.

We further agree that no change or addition to or other modification of the terms of the Contract or of the Works to be performed there under or of any of the Contract documents which may be made between you and the Contractor shall in any way release us from any liability under this guarantee, and we hereby waive notice of any such change, addition or modification.
This guarantee shall be valid until 30 days from the date of expiry of the Defects Liability Period.

Signature and seal of the guarantor _____
Name of Bank _____
Address _____
Date _____